2. The appointments are purely temporary, being borne on the Work Establishment of the Division, and are terminable without notice.

3. The applications should be in the form prescribed by the Central Recruitment Board, and should reach the undersigned on or before 1st April 1940.

4. These appointments are open to candidates of all communities.

G. SESHAGIRI RAO,
Superintending Engineer.

SHIMOGA DIVISION.

Abstract Notification dated 13th February 1940.

The attention of the public is drawn to the Notification, calling for tenders for restoring Balekoppa Doddakere, Major Tank, Register No. 120 of Kumsi Sub-Taluk, published in pages 378-379, Part VI of the *Mysore Gazette*, dated 22nd February 1940.

Tenders will be received by the Executive Engineer, Shimoga Division, up to 3 P.M. on 16th March 1940.

Earnest money required for the work is Rs. 235 which should be credited to the Treasury to "17 (*a*) P. W. Deposits" and chellan enclosed.

Abstract Notification dated 23rd February 1940.

The attention of the public is drawn to the notification calling for tenders for "constructing an Intermediate College at Shimoga" published in pages 438-441, Part VI of the *Mysore Gazette*, dated 29th February 1940.

Tenders will be received by the Executive Engineer, Shimoga Division, up to 3 P.M. on 18th March 1940.

Earnest money required for the work is Rs. 6,775 which should be credited to the Treasury to "17 (*a*) P. W. Deposits" and challan enclosed.

Notification dated 2nd March 1940.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 3 P.M., on 23rd March 1940, for restoring Dorligodu Minor Tank, Reg. No. 570 of Hiresara Village, Tirthahalli Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1940.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga Division, between the hours of 11 A.M. and 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer on payment of annas 4 for each form. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a treasury challan for Rs. 90 credited to Treasury under "17 (*a*) P. W. Deposits" as earnest money, and be superscribed "Tender for restoring Dorligodu Minor Tank, Reg. No. 570 of Heresara Village, Tirthahalli Taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Chamundy brand cement should be used for the work.

14. A reserve of 5 per cent on the value of work done will be withheld from the bills towards the security deposit.

Abstract estimate for restoring Hiresara Dorligodu Tank, Reg. No. 570 of Thirthahally Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
	I. Bund R. L. 56.00 top width 6′ slopes 2 : 1.		Rs. a. p.		Rs.
1	Clearing thick jungle and lantana growth on top and slopes of bund	S.yd.	0 0 3	2,222	
2	Cutting steps and grips in the breach and an old bund	L. S.	..	..	20
3	Clearing silt in the breach	C.yd.	0 2 6	55	
4	Earthwork to bund with watering, tamping, including consolidation average lead and lift, etc., complete	,,	0 6 0	1,720	
5	Consolidation charges for the earth used to bund	,,	0 1 6	25	
	Breach filling.				
6	Earthwork excavating foundation of puddle wall	C.yd.	0 4 0	16½	
7	Puddle wall mixed with good puddle clay and good gravel and well consolidated	,,	1 0 0	100	
8	(*a*) Turfing the slopes of bund	Sqr.	0 12 0	60·00	
	(*b*) Rough stone revetment	C.yd.	2 8 0	102	
9	Providing grade index Reg. No. and B. M. stones including dressing cutting, figures, painting, etc.	L. S.	..	..	33
	II. C. I. Pipe sluice.				
1	Earthwork cutting open the bund and refilling watering and tamping after constructing the sluice from R. L. 59·71 to 43·00	C.yd.	0 6 0	123	
2	Earthwork excavating foundation	,,	0 4 0	5	
3	Stone jelly concrete in cement mortar 1 : 4 : 8	C.ft.	0 7 0	104	
4	Size stone in cement mortar 1 : 6	,,	0 6 6	347	
5	Providing and fixing burnt stone slabs 6″ thick dressed and fixed in cement mortar	S.ft.	0 12 0	25	
6	Drilling holes in slabs	No.	1 0 0	4	
7	Stone jelly concrete in cement mortar 1 : 2 : 4	C.ft.	1 0 0	34	
8	Providing 4″ dia. C. I. pipe from Bhadravati including cost, railway fare, cart hire to spot, fixing, jointing, etc., complete 3 of 12′ long	R.ft.	2 4 0	36	
9	Providing and fixing teak wood plug and iron rod with locking arrangements, etc.	L. S.	..	..	15
10	Rough stone revetment apron in front and rear wherever required	C.yd.	2 8 0	5	
11	Cement plastering to inside walls and providing outside and other survey works	L. S.	..	..	48
	III. Waste Weir R. L. 50·00.				
1	Providing a natural waste weir 15′ long along the high sloping ground in hard laterite soil with side slopes of 1½ : 1 from R. L. 54·58 to 50·00	,,	..	..	100
	IV. Miscellaneous Works.				
1	Excavating a catch water drain to divert the surplus water coming from the side-hills and using the earth for training bank, etc.	,,	0 4 0	222	

D. A. HUKERI,
Executive Engineer.